

Switchboard Schedule

Project Reference: Room2, York **Job Number:** 10548 **Created By:** mscott **Rev Date:** 06/05/2026
Document No: 04480-SHK-02-ZZ-CA-E-10002 **Created On:** 11/08/2025 **Revised By:** mscott **Revision:** P02

Board Data

Id No: Sb-1	Name: Main Panel	L1	L2	L3
Model No:	Ze (Ω): 0.0262	Total Connected Load (A):	720.00	720.00
Board Rating (A): 800	Fault Rating (kA): 50	Total Diversified Load (A):	720.00	720.00
		Total Connected Generation (A):	0.00	0.00

Cables															
Phase	IdNo: Name:	Load (A) Diversified Connected	PF	3rd Harmonic %	Protective Device (A)		RCD mA	AFDD	Cable mm ²	Cores	Cable Type	Sep.CPC mm ²	Length (m)		
L1,L2,L3	Cbl_FC-533 Passenger Lift 1	16.0 16.0	0.88	0.00	40	16	MCCB	N/A	N/A	4	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	10	60	
L1,L2,L3	Cbl_FC-539 Passenger Lift 1	16.0 16.0	0.88	0.00	40	16	MCCB	N/A	N/A	4	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	10	60	
L1,L2,L3	Cbl_FC-540 Goods Lift	16.0 16.0	0.88	0.00	40	16	MCCB	N/A	N/A	4	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	10	60	
L1,L2,L3	Cbl_FC-573 PV	27.0 27.0	1.00	0.00	40	40	MCCB	N/A	N/A	25	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	70	
L1,L2,L3	Cbl_SM-15 Submain to DB/APT/GF	60.2 60.2	0.90	0.00	100	100	MCCB	N/A	N/A	35	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	25	
L1,L2,L3	Cbl_SM-46 Submain to DB/APT/1ST FLOOR	154.0 154.0	0.90	0.00	160	160	MCCB	N/A	N/A	95	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	28	

Switchboard Schedule

Project Reference: Room2, York

Job Number: 10548

Created By: mscott

Rev Date: 06/05/2026

Document No:

Created On: 11/08/2025

Revised By: mscott

Revision: P02

Board Data

Id No: Sb-1

Name: Main Panel

Model No:

Ze (Ω): 0.0262

Total Connected Load (A):

L1	L2	L3
720.00	720.00	720.00

Board Rating (A): 800

Fault Rating (kA): 50

Total Diversified Load (A):

720.00	720.00	720.00
--------	--------	--------

Total Connected Generation (A):

0.00	0.00	0.00
------	------	------

Cables

Phase	IdNo: Name:	Load (A) Diversified Connected	PF	3rd Harmonic %	Protective Device (A)		Type	RCD mA	AFDD	Cable mm ²	Cores	Cable Type	Sep.CPC mm ²	Length (m)
L1,L2,L3	Cbl_SM-74 Submain to DB/APT/2ND FLOOR	154.0 154.0	0.90	0.00	160	160	MCCB	N/A	N/A	95	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	31
L1,L2,L3	Cbl_SM-90 Submain to DB/APT/3RD FLOOR	155.4 155.4	0.90	0.00	160	160	MCCB	N/A	N/A	95	1 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	34
L1,L2,L3	Cbl_SM-111 Submain to DB/APT/4TH FLOOR	98.0 98.0	0.90	0.00	100	100	MCCB	N/A	N/A	35	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	37
L1,L2,L3	Cbl_SM-125 Submain to DB/APT/5TH FLOOR	51.8 51.8	0.90	0.00	100	100	MCCB	N/A	N/A	35	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	40
L1,L2,L3	Cbl_SM-126 Submain to DB/Kitchen	96.4 96.4	0.90	0.00	160	125	MCCB	N/A	N/A	50	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	25
L2	Cbl_SM-132 Submain to DB/LL/5th Floor	10.6 10.6	0.90	0.00	40	40	MCCB	N/A	N/A	10	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	46

Switchboard Schedule

Project Reference: Room2, York

Job Number: 10548

Created By: mscott

Rev Date: 06/05/2026

Document No:

Created On: 11/08/2025

Revised By: mscott

Revision: P02

Board Data

Id No: Sb-1

Name: Main Panel

Model No:

Ze (Ω): 0.0262

Total Connected Load (A):

L1	L2	L3
720.00	720.00	720.00

Board Rating (A): 800

Fault Rating (kA): 50

Total Diversified Load (A):

720.00	720.00	720.00
--------	--------	--------

Total Connected Generation (A):

0.00	0.00	0.00
------	------	------

Cables

Phase	IdNo: Name:	Load (A) Diversified Connected	PF	3rd Harmonic %	Protective Device (A)		Type	RCD mA	AFDD	Cable mm ²	Cores	Cable Type	Sep.CPC mm ²	Length (m)
L2	Cbl_SM-133 Submain to DB/LL/4th Floor	13.6 13.6	0.90	0.00	40	40	MCCB	N/A	N/A	10	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	43
L1	Cbl_SM-134 Submain to DB/LL/3rd Floor	26.5 26.5	0.90	0.00	40	40	MCCB	N/A	N/A	10	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	40
L2	Cbl_SM-135 Submain to DB/LL/2nd Floor	26.5 26.5	0.90	0.00	40	40	MCCB	N/A	N/A	10	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	37
L1	Cbl_SM-136 Submain to DB/LL/1st Floor	26.5 26.5	0.90	0.00	40	40	MCCB	N/A	N/A	10	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	34
L1,L2,L3	Cbl_SM-138 Submain to DB/LL/ Basement	41.3 41.3	0.90	0.00	100	100	MCCB	N/A	N/A	25	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	10
L1,L2,L3	Cbl_SM-140 Submain to DB/LL/GF	57.0 57.0	0.90	0.00	160	125	MCCB	N/A	N/A	35	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	N/A	31

Switchboard Schedule

Project Reference: Room2, York

Job Number: 10548

Created By: mscott

Rev Date: 06/05/2026

Document No:

Created On: 11/08/2025

Revised By: mscott

Revision: P02

Board Data

Id No: Sb-1

Name: Main Panel

Model No:

Ze (Ω): 0.0262

Total Connected Load (A):

L1	L2	L3
720.00	720.00	720.00

Board Rating (A): 800

Fault Rating (kA): 50

Total Diversified Load (A):

720.00	720.00	720.00
--------	--------	--------

Total Connected Generation (A):

0.00	0.00	0.00
------	------	------

Cables															
Phase	IdNo: Name:	Load (A) Diversified Connected	PF	3rd Harmonic %	Protective Device (A)			RCD mA	AFDD	Cable mm ²	Cores	Cable Type		Sep.CPC mm ²	Length (m)
					In	Ir	Type								
L1,L2,L3	Cbl_SM-141 Submain to DB/PLANT/2	305.0 305.0	0.90	0.00	400	400	MCCB	N/A	N/A	150	2 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)		N/A	75
L1,L2,L3	Cbl_SM-142 Submain to DB/PLANT/1	74.8 74.8	0.90	0.00	160	100	MCCB	N/A	N/A	35	1 x 1 x 5c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)		N/A	20
L3	Cbl_SM-143 Submain to DB/ LAUNDRY	58.8 58.8	0.90	0.00	100	80	MCCB	N/A	N/A	16	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)		N/A	55
L2	Cbl_SM-144 UPS FEED	66.1 66.1	0.93	0.60	100	100	MCCB	N/A	N/A	25	1 x 1 x 3c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)		N/A	10

Switchboard Schedule

Project Reference: Room2, York

Job Number: 10548

Created By: mscott

Rev Date: 06/05/2026

Document No:

Created On: 11/08/2025

Revised By: mscott

Revision: P02

Board Data

Id No: Sb-2

Name: 800A Switch Fuse

Model No:

Ze (Ω): 0.02167

Total Connected Load (A):

L1	L2	L3
720.00	720.00	720.00

Board Rating (A): 800

Fault Rating (kA): 50

Total Diversified Load (A):

720.00	720.00	720.00
--------	--------	--------

Total Connected Generation (A):

0.00	0.00	0.00
------	------	------

Cables

Phase	IdNo: Name:	Load (A) Diversified Connected	PF	3rd Harmonic %	Protective Device (A)			RCD mA	AFDD	Cable mm ²	Cores	Cable Type	Sep.CPC mm ²	Length (m)
					In	Ir	Type							
L1,L2,L3	Cbl_SM-36 Submain - Sw Fuse to Main Panel	720.0 720.0	0.90	0.00	800	N/A	Fuse	N/A	N/A	240	3 x 1 x 4c	Multicore 90°C thermosetting armoured *RUN TO 70°C Cu (4D4)	70	10